

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 30 1974
09-30-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Fred Cameron of H-30 Drilling, Inc. has this

date requested permission to plug the following described well:

Mr. James M. Stewart guarantees payment of the plugging fee.

Operator's full Name: James M. Stewart

Complete Address: 611 Union Center Bldg., Wichita, Kansas

Lease Name: Carter Well No. # 1

Location: SW SW SE Sec. 2 Twp. 12 Rge. 13 1/2 (E)(W) W

County: Russell Total Depth 3264 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Fred Cameron was instructed to plug the well as follows:

8 5/8" csg. 296' Cwc.

Circulated hole with heavy mud to 500', set plug, & displaced 50 sax

cement thru drill pipe. Mud to 280' & displaced 25 sax cement thru drill

pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 15 sax cement with

Allied Cementing Company's pump truck, cementing to base of cellar.

Very truly yours,

Don L. ...
Conservation Division Agent