

15-167-21958-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 23 1982  
FORM  
CONSERVATION DIVISION  
Wichita, Kansas  
08-09-82

State of Kansas



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

August 1, 1982

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Larry Hinderliter of Rains & Williamson Oil Co. has this date requested permission to plug the following described well:

Operator's Full Name: Rains & Williamson Oil Co. Inc.

Complete Address: 220 W. Douglas, Suite 435, Wichita, Kansas 67202

Lease Name: John Well No. 1

Location: SE SE SW Sec. 11 Twp. 12 Rge. 14 (E) (W)

County: Russell Total Depth: 3437'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Hinderliter was instructed to plug the well as follows:

Top Anhydrite 901' Fill hole and circulate with heavy mud.  
Pump 60 sacks cement through drill pipe at 600'. Pump 40 sacks  
cement through drill pipe at 300'. Fill hole with mud to 40'.  
Push plug and 1/2 sack hulls to 40' and Cap hole with 10  
Sacks cement. Cement rat hole with 10 sacks cement.

Very truly yours,

Arthur J. Larson  
Conservation Division Agent