

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 24 1969
CONSERVATION DIVISION
Wichita, Kansas
03-24-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Charles Harre of Brokan Arrow Drilling Company has this date requested permission to plug the following described well:

Mr. Forrest H. Lindsay guarantees payment of the plugging fee.

Operator's full Name: National Associated Petroleum Company

Complete Address: 4th. Floor, Petroleum Bldg., Tulsa, Oklahoma

Lease Name: Dora F. Kartman Well No. # 1

Location: NE SW NE Sec. 22 Twp. 17S 14 Rge. 14 (E) (W) W

County: Russell Total Depth 3210 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Charles Harre was instructed to plug the well as follows:

8 5/8" 257' Cwc.

Circulated hole with heavy mud to 500', set plug, & displaced 40 sax

cement thru drill pipe. Mud to 240' & displaced 25 sax cement thru

drill pipe. Mud to 40', set plug with 1/2 sax hulls, & displaced 10 sax

cement with Globe Cementing Company's pump truck, cementing to base of

cellar.

Very truly yours,

Don L. Lusk
Conservation Division Agent