

State of Kansas



FORM CP-2

JOHN CARLIN Governor  
R. C. LOUX Chairman  
JANE T. ROY Commissioner  
PHILLIP R. DICK Commissioner  
CAROL J. LARSON Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 07 1982  
CONSERVATION DIVISION  
Wichita, Kansas 1007-82

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Ed Cook of Thunderbird Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Thunderbird Drilling, Inc.

Complete Address: 7701 E. Kellogg, Suite 790, Box 19407, Wichita, Ks. 67218

Lease Name: Teppe Well No. 1

Location: NE NW NE Sec. 28 Twp. 12 Rge. 14 (E) (W)

County: Russell Total Depth: 3215'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Cook was instructed to plug the well as follows:

8 5/8" - 441' SP. circ. w/ 225 sacks common - 2% Cel. - 3% Col. Cl.  
Ordered 140 sacks 50 permix - 4% Cel. - 3% Col. Cl. + 8 5/8" plug. Spot w/ drill stem  
w/ heavy mud between all plugs. 1st plug @ 660' w/ 80 sacks.  
2nd plug @ 450' w/ 40 sacks.  
3rd plug - solid bridge of balls + plug @ 40' w/ 10 sacks.  
Circulate 10 sacks in rat hole.

Very truly yours,

[Signature]  
Conservation Division Agent