

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SE NW NE

SEC. 36 TWP. 10 RGE. 17

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Brungardt

Operator Helmerich & Payne Inc. Address Liberal, Kans ^{Box 253 Garden City, Mo.}

Field _____ County Rooks

Total Depth 3540 Feet.

Plugging Contractor Peel Bros Drg Co & Halliburton Cementing Co

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 258' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at 550', displaced 25 sax cement through drill pipe at 550', heavy mud to 240', set cementing plug and displaced 15 sax cement through drill pipe at 240', heavy mud to 40', set cementing plug, 1/2 sack huls and 10 sax cement to bottom cellar.

John Lee
District Conservation Agent

Date 7-29-57

STATE OF KANSAS
7-31-57
JUL 31 1957

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 36 T. 10 R. 17W
BOOK PAGE 32 LINE 33