

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Champlin Petroleum Company

Complete Address Box 308 Ellinwood, Kansas 67526

Lease Name Brungardt "A" Well No. 2

Location NW SW SW Sec. 36 Twp. 10 Rge. (E) (W) 17

County Rooks Total Depth 3642'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by HOWCO

Address License No.

Operation Completed: Hour 1:30 P Day 3 Month 4 Year 1972

The above well was plugged as follows:

Total Depth 3642' 8 5/8 csg set at 240' cwc:

5 1/2 csg set at 3600' cw 150 sk cmt.

5 1/2 csg PBDT 3572 and perf. (3524-3553)

5 1/2 csg DOC squeeze at 1095' W/150 sk. No pipe recovered.

ran 104 jts tbgs set at 3175' -pumped 100 lbs hulls & 25 sk gel & water -displaced

25 sk cmt. Pulled tbgs (86 jts) set at 550' -circ 65 sk cmt to surface. Pulled

remaining 18 jts tbgs.

Pumped 50 sk cmt down annulus.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 4-4-72

INV NO. 5488-W

Rec'd
Feb 7, 1972
KCC