

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 3 - 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Champlin Petroleum Company

Complete Address Box 308 Ellinwood, Kansas 67526

Lease Name Brungardt Well No. 6

Location SE NW SE Sec. 35 Twp. 10 Rge. (E) (W) 17

County Rooks Total Depth 3595'

Abandoned Oil Well ~~XXXX~~ Gas Well Input Well XXX SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by HOWCO

Address License No.

Operation Completed: Hour 1 P Day 28 Month 3 Year 1972

The above well was plugged as follows:

Total Depth 3595' 8 5/8 csg set at 155' cwc 125 sk.

5 1/2 csg set at 3594' cw 175 sk cmt.

PBTD 3567' and perf. (3477-3495)

5 1/2 csg squeezed at 709' with 348 sk cmt. No. pipe recovered.

Ramp 104 jts tbg (3175') pumped 25 sk gel & water W/100 lbs hulls -displaced 25 sk cmt.

Pulled 87 jts tbg to 510' circulated 60 sk cmt to surface.

Pulled remaining 17 jts tbg.

Checked anulus - cmt at surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4-3-72

INV. NO. 5458-W

Signed: L. J. Mansue
Well Plugging Supervisor