

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
4-19-72  
APR 19 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Champlin Petroleum Company

Complete Address Box 308 Ellinwood, Kansas 67526

Lease Name Brungardt Well No. 7

Location NW SW SE Sec. 35 Twp. 10 Rge. (E) (W) 17

County Rooks Total Depth 3650'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor        Co tools by HOWCO

Address        License No.       

Operation Completed: Hour 12:30 P Day 14 Month 4 Year 1972

The above well was plugged as follows:

Total Depth 3650' 8 5/8 csg set at 160' cwc. Cmt. Mat. "Halco-Light"

5 1/2 csg set at 3648' cw 150 sk cmt.

5 1/2 csg PBSD 3607' and perf. (3552-3557)

5 1/2 csg squeezed at 815' W/1490 sk cmt. No pipe recovered.

Ram 104 its tbg set at 3175' -pumped 25 sk gel & water W/100 lbs hulls -displaced

25 sk cmt. Pulled 84 its tbg set at 600' -circ 55 sk cmt to surface. Pulled

remaining 20 its tbg -capped 5 1/2 csg W/5 sk cmt.

Checked anulus with 1000 lbs. pres.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massery  
Well Plugging Supervisor

INVOICED

DATE 4-19-72

INV. NO. 5589-W