

15-163-03570-0000

Form CP-3
Rev. 6-4-68

KANSAS

P STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
4-6-72
APR 6 - 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Champlin Petroleum Company

Complete Address Bpx 308 Ellinwood, Kansas 67526

Lease Name Brungardt Well No. 8

Location SE SW SE Sec. 35 Twp. 10 Rge. (E) (W) 17

County Rooks Total Depth 3590'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. tools by HOWCO

Address License No.

Operation Completed: Hour 12 N Day 4 Month 4 Year 1972

The above well was plugged as follows:

Total Depth 3590' 8 5/8 csg set at 120' cwc 75 sk. Cmt. Mat. Halico-Light.

5 1/2 csg set at 3590' cw 150 sk cmt.

5 1/2 csg PBD 3526' with perf. (3482-3502') No pipe recovered.

5 1/2 csg squeezed at 684'-707' with 50 sk cmt 20% calseal, mixed with oil & gel.

Ran 104 jts tbg set at 3175' -pumped 25 sk gel & water W/100 lbs hulls, displaced

25 sk cmt. Pulled 87 jts tbg set at 510' circ 55 sk cmt to surface.

Pressured on anulus with 800 lbs. No ...

Layd down remaining 17 jts tbg.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 4-6-72

INV. NO. 5500-W