

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
4-14-72
APR 14 1972

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Champlin Petroleum Company
Complete Address Box 308 Ellinwood, Kansas 67526
Lease Name Brungardt Well No. 10
Location NE SE SW Sec. 35 Twp. 10 Rge. (E) (W) 17
County Rooks Total Depth 3535'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Co. Tools by HOWCO
Address License No.
Operation Completed: Hour 12:30 P Day 12 Month 4 Year 1972

The above well was plugged as follows:

RTD 3535' 8 5/8 csg set at 112' cwc Cmt. Mat. "Halco-Light".

5 1/2 csg set at 3532' cw 200 sk cmt.

5 1/2 csg squeezed at 648' W/250 sk. Unable to squeeze csg leak (843-996)

Overshot & jars on top of tbg -top of tubing @3420'

Ran 28 jts tbg set at 810' -Pumped 10 sk gel & water W/100 lbs hulls -displaced 25 sk cmt. -Pulled tbg (12 jts) set at 480' circ 45 sk cmt to surface. -Pulled remaining

16 jts tbg & capped 5 1/2 csg W/5 sk cmt.

Pumped 10 sk cmt down anulus with 150 lbs pres.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/17/72INV. NO. 5559-W

Signed: Geo F. Murray
Well Plugging Supervisor