

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-163-20,627-0000

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name EDMISTON OIL COMPANY

Complete Address 800 VICKERS - N.S.B. + T. BLDG. - WICHITA, KS. 67202

Lease Name WIKISMAN Well No. #3

Location C-N¹/₂ - NE - NE Sec. 35 Twp. 10^S Rge. 17^W (East) (West)

County ROOFS Total Depth 3700 FE

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor HELSE CASING PULLING (MILLARD HELSE)

Address BOX 412 - CHASE, KANS. License No. _____

Operation Completed: Hour: 1:15 PM Day: 28 Month: APRIL Year: 1981

The above well was plugged as follows:

8 5/8" 263 FE SR CUL - 1/200ST CNT. -> 5 1/2" SET @ 3699 FE
PLUG. BACK. 3660 FE -> PERK'S TOP 3586 FE SHOT TWICE - REC. 2684 FE
SAND BOTTOM TO 3000 FE AND 5ST CNT.
ORDERED 140ST 50% PERMIX 6% GEL. -> 22ST GEL. -> 4ST HULLS + 8 5/8" PLUG.
PUMPED IN 8 5/8" WITH PUMP TRUCK.
PWT. IN 3ST HULLS - 14ST GEL. -> 70ST CNT. -> 8ST GEL.
RELEASED PLUG. AND 70ST CNT. -> MAX. PRESSURE 300 LBS

CEMENTED BY SUN ENT
RECEIVED
4-29-81
APR 29 1981
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Conservation Division Agent

INVOICED

DATE 5-15-81

INVOICE NO. 5345-W