

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1978
CONSERVATION DIVISION
WICHITA, KANSAS
(or this well)

Operator's Full Name Tenneco Oil Co.Complete Address Suite 130-Ciudad Bldg., 3000 United Founders Blvd., Oklahoma City
Oklahoma 73112Lease Name Williams Field WF Unit Well No. 3-5Location SE NE NE Sec. 8 Twp. 10 Rge. (E) (W) 18County Rooks Total Depth 3752Abandoned Oil Well Gas Well Input Well XX SWD Well D & A Other well as hereafter indicated Plugging Contractor Kelso Casing PullingAddress Box 176, Chase, Kansas 67524 License No. 683Operation Completed: Hour 10:30 A Day 16 Month 5 Year 1978

The above well was plugged as follows:

Total Depth 3752' 10 3/4 csg set 1593' cwc 1300 sk.7" csg set 3748' cw 200 sk cem.7" csg PBTD 3732' with perf. (3633'-3313')Set 7" wwd plug at 3300' -poured 10' sd-dumped 5 sk cem. W/dump bailer. (3300'-3260')Cutoff & recovered 2300' of 7" csg.Drlg. mud to 575' -sand & rock bridge (575'-555')Filled with readymix cement from 555' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Messer
Well Plugging SupervisorDATE 5-17-78INV. NO. 7321-W