

KANSAS

Y
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
10-20-67
OCT 20 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Tenneco Oil Company
Complete Address: 2000 Classen Center, N. Bldg. Oklahoma City, Okla. 73106
Lease Name Williams Fld. W. Fldod Well No. 3-3
Location SE ^{NW} NE Sec. 8 Twp. 10 Rge. 18 (E) (W) X
County Rooks Total Depth 4113
Abandoned Oil Well Gas Well Input Well X SWD Well X D & A
Other well as hereafter indicated:
Plugging Contractor: Co. Tools by HOWCO
Address: Hays, Kansas License No.
Operation Completed: Hour 10:30 ^P Day 16 Month 10 Year 1967

The Above well was plugged as follows:

Total Depth 4113' 8 5/8 csg set at 1586' cwc 800 sc.
5 1/2 csg set at 3937' cw 200 sc cement. No Recovery
2" tubing stuck on bottom. Shot off and recov. 3391' of same., left in hole (3391-3937)
Pumped down 5 1/2 csg with 100 sc cement, plug and 30 sc gel & hulls, plug and 100 sc cement.
Pumped down annulus (8 5/8-5 1/2) with 150 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Prof. Massey
Well Plugging Supervisor

DATE 10/20/67
INV. NO. 6531-W