

15-163-20029-0000

Form CP-3
Rev. 6-1-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
7-12-76
JUL 12 1976

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

CONSERVATION DIVISION
Wichita (of this well)

Operator's Full Name Tenneco Oil Company

Complete Address Ciudad Building, Suite 139, 3000 United Founders Boulevard

Oklahoma City, Oklahoma 73112

Lease Name Williams Field Waterflood Well No. 3-7

Location S/2 SE NW NE Sec. 8 Twp. 10 Rge. (E) (W) 18

County Rooks Total Depth 4173'

Abandoned Oil Well Gas Well Input Well ~~XX~~ SWD Well X D & A

RT
KCC

Other well as hereafter indicated

Plugging Contractor Tenneco Oil Co. by "Hallib."

Address License No.

Operation Completed: Hour 6 P Day 9 Month 7 Year 1976

The above well was plugged as follows:

Total Depth 4173' 8 5/8 csg set 271' cwc 225 sk.

5 1/2 csg set 3999' cw 610 sk. cem. 5 1/2 csg sq. 1560' to base of cellar.

KC perf. (3700'-3200') No pipe recovered.

Set 2 1/2" tbg 3992' -circ 27 sx gel & water W/500 lbs hulls -disp. 50 sk cem. 4% gel.

Pulled 2 1/2" tbg to 3700' -displaced 110 sk cem 4% gel.

Pulled 2 1/2" tbg to 600' -circ 8 sk gel & water W/300 lbs gel. circ 120 sk cem. 4% gel

Pulled 2 1/2" tbg. -filled displacement with 20 sk cem to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Les Massey
Well Plugging Supervisor

DATE 7-14-76

INV. NO. 3463-N