

15-163-20008-0000

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
5-2-78
MAY 02 1978
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Tenneco Oil Co.

Complete Address Suite 139, Ciudad Bldg., 3000 United Founders Blvd., Oklahoma City,
Oklahoma 73112

Lease Name Williams Field WUnit Well No. 4-3

Location E/2 SE NE SE Sec. 8 Twp. 10 Rge. (E) (W) 18

County _____ Rooks _____ Total Depth 3781'

Abandoned Oil Well _____ Gas Well _____ Input Well XX SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas License No. 683

Operation Completed: Hour 2:30 P Day 26 Month 4 Year 1978

The above well was plugged as follows:

Total Depth 3781' 8. 5/8 csg set 1586' cwc 800 sk.

5 1/2 csg set 3781' cw 150 sk.

5 1/2 csg PBDT 3769' with perf. (3642'-3320')

Set 5 1/2 wood plug at 3300' -poured 10' sd- dumped 5 sk cem. W/dump bailer. (3300'-3260')

Cutoff & recovered

Drlg. mud to 575'- set rock & sand bridge (575'-560')

Filled with readymix cem. from 560' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5-2-78

INV. NO. 7224.0

Signed: Leo Massey
Well Plugging Supervisor