

15-163-02606-0000

Form CP-3  
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
9-18-72  
SEP 18 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Davis Bros.  
Complete Address 500 McFarlin Bldg., Tulsa, Oklahoma 67103  
Lease Name Garvet "I" Well No. 1  
Location SW SE SW <sup>RT KCC</sup> Sec. 13 Twp. 10 Rge. (E) (W) 18  
County Rooks Total Depth 3690'  
Abandoned Oil Well        Gas Well        Input Well XX SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Co. Tools by HOWCO.  
Address        License No.         
Operation Completed: Hour 12 N Day 12 Month 9 Year 1972

The above well was plugged as follows:

- Total Depth 3690' 8 5/8 csg set at 154' cwc 135 sk.
- 4 1/2 csg set at 3685' cw 275 sk cmt.
- 2" tbg set on packer at 2100'. No pipe recovered.
- Pumped down 2" tbg with 10 sk gel & water W/200 lbs hulls and 50 sk cmt.
- Pumped down 2" tbg-4 1/2 csg anulus with 85 sk cmt W/150 lbs hulls.
- Pumped down 4 1/2-8 5/8 anulus with 50 sk cmt W/150 lbs hulls.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 9/18/72  
INV. NO. 6325-W