

3 023197

15-207-02047-00-00

To:

API NUMBER 20070029-002-control#

STATE CORPORATION COMMISSION

SE,NE,NE 1/4 Sec/Twp/Rge S17-T.26S.-R.16E.

Wichita State Office Bldg. - PLUGGING SECTION

kcc 4051-4709 feet from south section line

130 S. Market, Room 2078

24P 230-1540 feet from east section line

Wichita, Kansas 67202

BUM01

TECHNICIAN'S PLUGGING REPORT

Lease/Well# BUMAN NO. 01

Operator License # 100101

County WOODSON

Operator: STATE OF KANSAS

Well Total Depth 1100' feet

Name & FEE FUND PLUGGING

Production Pipe: 4 1/2" Size Feet 1100'

Address

Surface Casing: 6" Size Feet 40'

AB oil well X Gas Well SWD Well/ Input Well

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. #

30870

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 8:00A.M. Day: 25 Month: 7 2007

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 4 1/2" CASING TO APPROXIMATELY 1100' THAT HAD

'BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO PERFORATE THE

CASING AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All Part

TECHNICIAN

None X

Operations Completed: Hour: 1:00P.M. Day: 25 Month: 7 2007

Actual Plugging Report: THE 4 1/2" CASING WAS PEFORATED AT 200' AND WAS

PERFORATED AT 700'. 1" PIPE WAS RAN INTO THE 4 1/2" CASING TO 1100'. CEMENT WAS

PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 4 1/2" CASING AT

SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

189 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (SPOT LOCTION ESTABLISHED BY GPS AS BUM 01)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel

TECHNICIAN RECEIVED
KANSAS CORPORATION COMMISSION

AUG 20 2007

CONSERVATION DIVISION
WICHITA, KS

33749

PST