

3 023336

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 100 101

Operator: STATE OF KANSAS

Name & FEE FUND PLUGGING

Address

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well

Other well as hereinafter indicated:

Plugging Contractor: K-W WELL SERVICE

Address: 19450 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 9:00 A.M. Day: 3 Month: 4 2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: VISIBLE AT SURFACE ON THIS WELL WAS 8" SURFACE CASING ONLY. THE

PLUGGING PROPOSAL WAS TO DRILL OUT THE WELL AND TO CIRCULATE AS MUCH

OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All ☒ Part

TECHNICIAN

None

Operations Completed: Hour: 12:00 P.M. Day: 3 Month: 4 2008

Actual Plugging Report: A 4" BIT WAS UTILIZED TO DRILL OUT THE WELL TO 550'

1" PIPE WAS RAN INTO THE WELL TO 550'. CEMENT WAS PUMPED INTO THE 1" PIPE

UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE

WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 150 SACKS OF CEMENT

WERE PUMPED INTO THIS WELL.

RECEIVED
KANSAS CORPORATION COMMISSION

APR 14 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: (GPS SESSION POINT NO. CAN 09)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

PVT