

3 023321

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 100 101

Operator: STATE OF KANSAS

Name & FEE FUND PLUGGING

Address _____

AB oil well ☒ Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W OIL WELL SERVICE, INC.

Lic. # 3097

Address: 19450 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 8:00A.M. Day: _____ 3 Month: 3 2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: VISIBLE AT SURFACE ON THIS WELL WAS 8" DRIVE PIPE ONLY. THE PLUGGING

PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All ☒ Part _____

TECHNICIAN
None

Operations Completed: Hour: 12:00PM Day: _____ 3 Month: 3 2008

Actual Plugging Report: A 4" SWEDGE ON 1" PIPE WAS RAN INTO THE WELL TO 150'

WITHOUT ENCOUNTERING ANY OBSTRUCTION. THE SWEDGE WAS REMOVED. 1" PIPE

WAS RAN INTO THE WELL TO 425'. A SOLID OBSTRUCTION WAS ENCOUNTERED AT THAT

DEPTH. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM

THE 12" SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT

WAS FILLED FROM SURFACE. 123 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION POINT NO. 001) (NO OTHER DATA IS AVAILABLE.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION Signed: _____

MAR 21 2008

CONSERVATION DIVISION
WICHITA, KS

Clayton P. Titel
TECHNICIAN

pet