

3 023323

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 100 101

Operator: STATE OF KANSAS

Name & FEE FUND PLUGGING

Address _____

AB oil well ☒ Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: KW OIL WELL SERVICE, INC

Lic. # 3097

Address: 19450 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 8:00A.M. Day: _____ 19 Month: 3 2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2285

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT MAY

HAVE BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS

TO PERFORATE THE CASING AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE

FULL OF CEMENT.

Plugging Proposal Received by: _____

CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____

TECHNICIAN

None ☒

Operations Completed: Hour: 10:00A.M. Day: 19 Month: 3 2008

Actual Plugging Report: THE CASING WAS PERFORATED AT 500' AND AT 200'. 1"

PIPE WAS RAN INTO THE 2" CASING TO 750'. CEMENT WAS PUMPED INTO THE 1" PIPE

UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED.

DISPLACEMENT WAS FILLED FROM SURFACE. 21 SACKS OF CEMENT WERE PUMPED

INTO THIS WELL.

RECEIVED

KANSAS CORPORATION COMMISSION

Remarks: _____

(If additional description is necessary, use BACK of this form.)

MAR 31 2008

CONSERVATION DIVISION
WICHITA, KS

I DID NOT observe this plugging.

Signed: _____

Clayton P. Titel
TECHNICIAN

[Handwritten signature]