

3 023324

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 100 101Operator: STATE OF KANSASName & FEE FUND PLUGGING

Address _____

AB oil well ☒ Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: KW OIL WELL SERVICE, INCLic. # 3097Address: 19450 FORD RD., CHANUTE, KS. 66720Company to plug at: Hour: 10:00A.M. Day: _____ 19 Month: 3 2008Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2285Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT MAYHAVE BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WASTO PERFORATE THE CASING AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLEFULL OF CEMENT.

Plugging Proposal Received by: _____

CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____

TECHNICIAN

None ☒ XOperations Completed: Hour: 12:00P.M. Day: _____ 19 Month: 3 2008Actual Plugging Report: THE CASING WAS PERFORATED AT 500' AND AT 200'. 1"PIPE WAS RAN INTO THE 2" CASING TO 750'. CEMENT WAS PUMPED INTO THE 1" PIPEUNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED.DISPLACEMENT WAS FILLED FROM SURFACE. 22 SACKS OF CEMENT WERE PUMPEDINTO THIS WELL.

RECEIVED

KANSAS CORPORATION COMMISSION

Remarks: _____

MAR 31 2008

(If additional description is necessary, use BACK of this form.)CONSERVATION DIVISION
WICHITA, KS

I DID NOT observe this plugging.

Signed: _____

Clayton P. Titel
TECHNICIAN

PVT