

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER ²⁰⁶ ~~15-192-~~ 19727-00-00
NE SE NW Sec/Twp/Rge 16-29-17E
3892 (GPS) feet from south section line
2715 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: State Of Kansas Fee Funds
Name & Mary F. Douglas Lease Project
Address _____
AB oil well _____ Gas Well _____

Lease/Well# Douglas, Mary F. GPS #22
County Wilson
Well Total Depth 850 feet
Production Pipe: 2 Size Feet 850
Surface Casing: 10 Size Feet NA
SWD Well/ Input Well XXXXXX D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749
Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 3 Month: 2 2009

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: _____

Were: Clean well to TD and pump full of cement thru cement string.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All _____ Part _____ None XXXXXX

Operations Completed: Hour: _____ Day: 3 Month: 2 2009

Actual Plugging Report: A 1" cement string was washed down to 800' outside the 2" production pipe.

A 1" cement string was washed down the inside of the 2" production pipe to 850'. The well was pumped full of cement from btm to top thru these cement strings. A total of 240 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 19 2009

CONSERVATION DIVISION
WICHITA KS

Remarks: Control # 20090005-022. Could not find a record of this well in District III UIC files.
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed:

Alan M. Dunning
TECHNICIAN