

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-003-01688-00-00
^{NW} SW NE NE Sec/Twp/Rge Sec. 6, T21S, R20E
5145 feet from south section line
1181 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: STATE OF KANSAS
Name & FEE FUND
Address CHANUTE DISTRICT OFFICE
AB oil well _____ Gas Well _____ SWD Well/ Input Well _____

Lease/Well# BOWMAN / BOW50
County ANDERSON
Well Total Depth 840 feet
Production Pipe: 6-1/4 Size Feet NA
Surface Casing: 10 Size Feet EST 20
SWD; D-00875 D & A

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, INC. Lic. # 30670
Address: 19245 FORD ROAD, CHANUTE, KS 66720

Company to plug at: Hour: _____ Day: _____ 1 Month: APRIL 2008

Plugging proposal received from: MIKE KEPLEY

Company Name: KEPLEY WELL SERVICE, INC. Phone: (620) 431-9212

Were: FILL WELL WITH CEMENT FROM TD TO SURFACE.

Plugging Proposal Received by: _____

Plugging attended by Agent: All _____ Part _____ TECHNICIAN
None XXXXX

Operations Completed: Hour: _____ Day: _____ 1 Month: APRIL 2008

Actual Plugging Report: RUN 1 INCH INSIDE 6-1/4 INCH CASING TO 840 FEET AND RUN
1/2 INCH OUTSIDE TO 375 FEET AND PUMP PORTLAND CEMENT FROM TD TO SURFACE. PULL
PIPE AND TOP OFF WELL. PUMP TOTAL OF 442 SACKS OF CEMENT. WELL PLUGGED.

Remarks: CONTROL #20070042-050 GPS # BOW50 CONTRACT #10279
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed: Lei Shost 5/6/08
TECHNICIAN

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 08 2008

CONSERVATION DIVISION
WICHITA, KS