

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER ²⁰⁵ ~~15-123-~~ 19712-00-00
NW SE NW Sec/Twp/Rge 16-29-17E
3826 (GPS) feet from south section line
3368 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: State Of Kansas Fee Funds
Name & Mary F. Douglas Lease Project
Address _____

Lease/Well# Douglas, Mary F. GPS #07
County Wilson
Well Total Depth 800 feet
Production Pipe: 2 Size Feet 800
Surface Casing: 7 Size Feet NA
SWD Well/ Input Well _____ D & A _____

AB oil well XXXXXX Gas Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749
Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 5 Month: 2 2009

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: _____

Were: Clean well to TD and pump full of cement thru cement string.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All XXXXXX Part _____
TECHNICIAN None _____

Operations Completed: Hour: _____ Day: 5 Month: 2 2009

Actual Plugging Report: 800' of the 1" pumping string was removed along with the pump. The well was then perforated at 250' and 150'. A 1" cement string was lowered to 800' and the well pumped full of cement from btm to top thru this cement string. A total of 104 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED

MAR 2 2009

Remarks: Control # 20090005-007
(if additional description is necessary, use BACK of this form.)

KCC WICHITA

I did observe this plugging.

Signed: Alan M. Dunning
TECHNICIAN

PKC