

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER <sup>205</sup> ~~15-183-~~ 19713-00-00  
NW SE NW Sec/Twp/Rge 16-29-17E  
3500 (GPS) feet from south section line  
3409 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101  
Operator: State Of Kansas Fee Funds

Lease/Well# Douglas, Mary F. GPS #08  
County Wilson  
Well Total Depth 650 (est) feet

Name & Mary F. Douglas Lease Project  
Address

Production Pipe: 2 Size Feet 650 (est)  
Surface Casing: 12 Size Feet NA

AB oil well Gas Well XXXXXX

SWD Well/ Input Well D & A

Other well as hereinafter indicated:

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: Day: 14 Month: 1 2009

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone:

Were: Clean well to TD and pump full of cement thru cement string.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All Part XXXXXX None

Operations Completed: Hour: Day: 14 Month: 1 2009

Actual Plugging Report: The well had a string of 2" production pipe that was approx 50' down. The contractor was able to skirt over the 2" production pipe with a 50' string of 2" pipe and then wash down to 300' with a 1" cement string. A 1" cement string was also washed down the outside of the production pipe to 650'. The well was pumped full of cement from btm to top thru these cement strings. A total of 234 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Remarks: Control # 20090005-008  
(If additional description is necessary, use BACK of this form.)

I partially observed this plugging

Signed: Alan M. Dunning  
TECHNICIAN

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 05 2009  
CONSERVATION DIVISION  
WICHITA, KS

PKS