

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER ²⁰⁵ ~~15-123-~~ 19715-00-00
SW SE NW Sec/Twp/Rge 16-29-17E
2952 (GPS) feet from south section line
3637 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: State Of Kansas *Fee Funds*

Lease/Well# Douglas, Mary F. GPS #10
County Wilson
Well Total Depth 850 (est) feet

Name & Mary F. Douglas Lease Project
Address _____

Production Pipe: 4 Size Feet 850 (est)
Surface Casing: NA Size Feet NA

AB oil well XXXXXX Gas Well _____

SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 7 Month: 1 2009

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: _____

Were: Clean well to TD and pump full of cement thru cement string.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All XXXXXX Part _____ TECHNICIAN None _____

Operations Completed: Hour: _____ Day: 7 Month: 1 2009

Actual Plugging Report: A swedge was lowered to 300'. The swedge was removed and the well was then perforated at 250' and 150'. A 1" cement string was washed to 850' and the well pumped full of cement from btm to top thru this cement string. A total of 91 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Remarks: Control # 20090005-010

(If additional description is necessary, use BACK of this form.)

I did observe this plugging.

KANSAS CORPORATION COMMISSION

Signed:

Alan M. Dunning
TECHNICIAN

JAN 26 2009
RECEIVED

PKP