

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-~~123~~-19716-00-00 <sup>205</sup>  
SW SE NW Sec/Twp/Rge 16-29-17E  
2806 (GPS) feet from south section line  
3863 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101  
Operator: State Of Kansas Fee Funds  
Name & Mary F. Douglas Lease Project  
Address \_\_\_\_\_  
AB oil well XXXXXX Gas Well \_\_\_\_\_

Lease/Well# Douglas, Mary F. GPS #11  
County Wilson  
Well Total Depth 820 feet  
Production Pipe: 3 Size Feet 820  
Surface Casing: 10 Size Feet NA  
SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: \_\_\_\_\_ Hour: \_\_\_\_\_ Day: 29 Month: 12 2008

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: \_\_\_\_\_

Were: Clean well to TD and pump full of cement thru cement string.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXX  
TECHNICIAN

Operations Completed: Hour: \_\_\_\_\_ Day: 29 Month: 12 2008

Actual Plugging Report: A 1" cement string was washed down the inside of the 3" production pipe to 820'. A 1" cement string was washed down the outside of the 3" production pipe to 500'. The well was pumped full of cement from btm to top thru these cement strings. A total of 230 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 23 2009

CONSERVATION DIVISION  
WICHITA, KS

Remarks: Control # 20090005-011  
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed: Alan M. Dunning  
TECHNICIAN

*Handwritten initials: PPS*

*Handwritten circle mark*