

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-121- 01802-00-00
NENWSW Sec/Twp/Rge 25-16S-21E
2226 feet from south section line
4078 feet from east section line

8

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# DUNN ~~GPS#14~~ #14

County MIAMI

Operator: STATE OF KANSAS

Well Total Depth 650 EST. feet

Name & FEE FUND

Production Pipe: 2 Size Feet 650 EST.

Address _____

Surface Casing: 10 Size Feet 20 EST.

AB oil well X Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W OIL WELL SERVICES, INC. Lic. # 3097

Address: 19450 FORD ROAD CHANUTE, KS. 66720

Company to plug at: Hour: _____ Day: _____ 8 Month: NOV 2006

Plugging proposal received from: SAM KEPLEY

Company Name: KW OIL WELL SERVICES, INC. Phone: 620-496-7173

Were: PLUG WELL WITH PORTLAND CEMENT, TD TO SURFACE.

Plugging Proposal Received by: FRANK GUILFOYLE

Plugging attended by Agent: All X Part _____
TECHNICIAN
None _____

Operations Completed: Hour: _____ Day: _____ 9 Month: NOV 2006

Actual Plugging Report: CLEAR LOCATION TO AND AROUND WELL. DIG AROUND 2" AND SET SURFACE. RUN 1" TO 500 FT INSIDE 2". WASH 1" TO 550 FT OUTSIDE 2". PUMP PORTLAND CEMENT FROM TD TO SURFACE. PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 168 SACKS OF CEMENT. WELL PLUGGED.

Remarks: CONTROL # 20060060-032 GPS# DUN14 CONTRACT # 09569
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: FRANK GUILFOYLE
TECHNICIAN

PK

RECEIVED
NOV 20 2006
KCC WICHITA