

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21505-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 21-27S-16W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: CLARK Well #: 1
County: KIOWA Total Vertical Depth: 4700 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	450		WITH 300 SX CMT
PROD	4.5	4697	2350	WITH 100 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/14/2009 1:18 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: BRANDON SIROKY Company: OIL PRODUCERS INC. OF KANSAS Phone: (316) 215-1357

Proposed Plugging Method: SAND BACK TO 4500' WITH 4 SX CMT. PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. PLUG AT 480' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

152.75

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/14/2009 2:50 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED TO 4500' WITH 4 SX CMT. 1ST PLUG AT 1100' WITH 15 SX GEL, 50# HULLS, & 50 SX CMT. 2ND PLUG AT 480' WITH 50# HULLS & 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4612	4617		KINDERHOOK
4556	4676		MISSISSIPPI

INVOICED
DATE 6-26-09
INV. NO. 2009061630

RECEIVED
MAY 26 2009

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

KCC WICHITA

District: 01

RECEIVED

MAY 18 2009

KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)

PKT

RAWY