

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-197-20280-00-00
Spot: NWSWSENE Sec/Twnshp/Rge: 2-13S-10E
3250 feet from S Section Line, 1100 feet from E Section Line
Lease Name: THOWE D NORTH Well #: 04-08
County: WABAUNSEE Total Vertical Depth: 3050 feet

Operator License No.: 30345
Op Name: PIQUA PETRO, INC.
Address: 1331 XYLAN RD
PIQUA, KS 66761

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	315		165 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/15/2008 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: BEN HEROLD Company: SKYY DRILLING Phone: _____

Proposed Plugging Method: 50' PLUG AT THE HUNTON, 50' PLUG AT THE VIOLA, 50' PLUG AT THE MISSISSIPPI, 50' PLUG AT THE KANSAS CITY, AND CEMENT FROM 350' TO SURFACE.

99.13

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 12/15/2008 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

SPOTTED 50' PLUG AT TD. PULLED THE PIPE UP TO 2700' AND PUMPED 15 SACKS OF CEMENT. PULLED THE PIPE UP TO 2210' AND PUMPED 15 SACKS OF CEMENT. PULLED THE PIPE UP TO 1455' AND PUMPED 15 SACKS OF CEMENT. PULLED THE PIPE UP TO 350' AND PUMPED 95 SACKS OF CEMENT TO THE SURFACE. PUMPED 15 SACKS OF CEMENT IN THE RAT HOLE.

Perfs:

RECEIVED
KCC DISTRICT #3

MAY 5 2009 TCH

CHANUTE, KS

INVOICED

DATE 6-26-09

INV. NO. 2009061631

Remarks:

Plugged through: DP

District: 03

Signed Taylor C. Herman
(TECHNICIAN)

PKT

RECEIVED

MAY 26 2009

KCC WICHITA