

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-181-20029-00-00
Spot: SENW Sec/Twnshp/Rge: 15-6S-42W
3280 feet from S Section Line, 3280 feet from E Section Line
Lease Name: PIZEL Well #: 1
County: SHERMAN Total Vertical Depth: 5576 feet

Operator License No.: 33019
Op Name: ROSEWOOD RESOURCES, INC.
Address: 2101 CEDAR SPRGS RD, STE 1500
DALLAS, TX 75201

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	350	0	w/225 sxs cmt
PROD	4.5	1925	0	w/unknown sxs cmt

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/13/2009 10:00 AM
Plug Co. License No.: 33532 Plug Co. Name: ADVANCED DRILLING TECHNOLOGIES LLC
Proposal Rcvd. from: TOM ROELFS Company: ROSEWOOD RESOURCES, INC. Phone: (970) 848-0799

Proposed Plugging Method: Ordered 250 sxs common cement.
Plug through casing.

181.22

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/13/2009 11:00 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 350' w/225 sxs cement.
4 1/2" production casing set at 1925' w/unknown sxs cement.
TD 5576'. Perforations in Niobrara - footage is unknown.
Connected to 4 1/2" production casing - pumped 131 sxs cement.
Max. P.S.I. 900#. S.I.P. 350#.
Connected to 8 5/8" surface casing - pumped 22 sxs cement.
Casing ruptured under braden head.
Max. P.S.I. 400#. S.I.P. 0#.

Perfs:

INVOICED
DATE 6-26-09
INV. NO. 2009061634

Remarks: ADT CEMENT SERVICE-TICKET #1993.

Plugged through: CSG

RECEIVED
MAY 26 2009
KCC WICHITA
PKT

District: 04

Signed

Darrel Dipman
(TECHNICIAN)

CM

SKJ

38095091830
E. 3000

PLAINS RESOURCES, INC.
2502 1ST NAT'L CTR.
OKLAHOMA CITY, OK. 73102

REPLACEMENT CARD:

15-6-42W
C. SE. NW

#1 PIZEL


CONTR EMPIRE DRILLING COMPANY CTV SHERMAN

GEOL

FIELD WC(14-3/4' SW OF RUEB) SO.

E 3796 KB CM 12/26/77 CARD ISSUED 7/28/79 IP ^{ABD} D&A/MRW

2/1/79



API 15-181-20,029

LOG	TOPS	DEPTH	DATUM
NI OB		1640	+2156
DAK		2530	+1266
BLAINE		3328	+ 468
CO GR		3930	- 134
TOP		4116	- 320
HEEB		4440	- 644
KC		4496	- 700
MARM		4858	-1062
MRW		5300	-1504
RTD		5576	-1780

8-5/8" 350/225sx

DST (1) 1800-1965 (NI OB)/30-60-30-60,
REC 30' M, SIP 541-527#, FP 102-102/102-112#, HP 951-931#

DST (2) 2114-2184 (DAK)/30-60-30-60,
REC 25' M, SIP 608-547#, FP 51-61/61-61#, HP 1072-1052#

DST (3) 3363-3391 (BLAINE)/MISRUN

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

INFO RELEASED: 12/31/80 WAS OPERATIONS SUSPENDED