

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-20860-00-00
Spot: SENE Sec/Twnshp/Rge: 10-29S-13W
1830 feet from N Section Line, 510 feet from E Section Line
Lease Name: TROUT-LILLY Well #: 1
County: PRATT Total Vertical Depth: 4776 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4480		WITH 2 SX CMT
CIBP		4568		
SURF	8.625	485		WITH 400 SX CMT
PROD	5.5	4775	1510	WITH 160 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/13/2009 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (625) 938-2537

Proposed Plugging Method: CIBP @ 4480' & 2 SX CMT. PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. PLUG AT 510' WITH 50 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

155.22

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/13/2009 11:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PACKER & PLUG LEFT IN HOLE @ 4670'. SET CIBP @ 4480' & PUT 2 SX CMT ON TOP OF CIBP WITH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 510' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4736	4742		ARBUCKLE
4630	4632		SIMPSON
4524	4530		VIOLA
4517	4521		VIOLA

INVOICED

DATE 6-26-09
INV. NO. 2009061636

RECEIVED

MAY 26 2009

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

RECEIVED

MAY 21 2009

KCC DODGE CITY

Signed

Stephen J. Pfeifer
(TECHNICIAN)

PKT

RAW