

5-2

6 070836

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-063-20844-00-00

SE SE SW, SEC. 17, T 11 S, R 31 W
330 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5123
Operator: Pickrell Drilling Co. Inc.
Name & Address: 110 N. Market #205
Wichita, Ks. 67202
C/O Danny Biggs

Lease Name McDonald Well # A #1
County Gove 150.64
Well Total Depth 4635 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 252

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number
Address Box 420 Ness City, Ks. 67560

Company to plug at: Hour: 2:00PM Day: 2 Month: May Year: 19 90

Plugging proposal received from Ed Mondero

(company name) Pickrell Drilling (phone)

were: 8 5/8" 252' s.p. cwc w/170 sks. 4 1/2 casing set at 4629 w/175 sks.
D.V. tool at 2466' cwc w/800 sks cement. Perfs at 4565 to 4120. Casing good. Proposal

225 sks 65/35 poz 8% gel and 5 sks hulls. Pumped in with pump truck. Load both 4 1/2 casing and 4 1/2 x 8 5/8 annulus with cement. Shut in under pressure.

Plugging Proposal Received by *MJS* Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:00PM Day: 2 Month: May Year: 19 90

ACTUAL PLUGGING REPORT Pickrell ordered 225 sks 65/35 poz 8% gel and 5 sks hulls. Pumped in with pump truck. 1. Annulus cement visible at surface. (D.V. at 2466 w/800 sks cement)

2. In 4 1/2 casing pumped in 15 sks cement followed with 170 sks cement w/5 sks hulls added in. Max pressure 1800 psig. Shut in 950 psig.

Cemented by Allied Cementing. Ness City, Ks.

Remarks: (If additional description is necessary, use BACK of this form.)

did not observe this plugging.

Signed *Marion J. Schmidt* (TECHNICIAN) Marion J. Schmidt

INVOICED

DATE 6-6-90

INV. NO. 28332

JUL 11 1990

FORM CP-2/3 Rev. 01-84

5-2