

6 010631

9-1 15-147-30094-00-00

KRC
afB
7-709

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 10-21-1965
NW, SEC. 20, T 244 S, R 18 W/E
feet from S section line
feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6242

Lease Name Stoneman Well # 6

Operator: Petroleum Mgmt. Inc.
Name & Address: 400 N. Woodlawn
Wichita, Ks.

County Phillips 108.88

Well Total Depth 3350 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 195

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Same License Number 5242

Address Same

Company to plug at: Hour: 9:00AM Day: 1 Month: Sept Year: 19 88

Plugging proposal received from Don Keener

(company name) Same (phone)

were: Order 200 sks 60/40 Poz 8% Gel w/1/2 sk F.C. 300# Hulls. 4 1/2" casing at 3348'

Squeezed at 690' w/200 sks. 1010' w/150 sks 984' - 1675' w/150 sks 931' w/50 sks.

Recovered 2000' of tubing. Elev. 1913'

SLD 1350'

Top 563' = 860'

Plugging Proposal Received by D.F.B. (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: Day: Month: Sept Year: 19

ACTUAL PLUGGING REPORT Ran tubing to 2000'. Pumped down tubing 60 sks cement w/100#

Hulls. Pulled 1000' of tubing. Pumped down tubing 50 sks cement w/100# Hulls.

Circulated. Pulled tubing. Pumped down 4 1/2" 25 sks cement w/100# Hulls. Max 700#

Closed 400#. Pumped down 8 5/8" 15 sks cement. Max 700# Close 500#. Allied

Cement Co. Checked plug Sept. 6, 1988 O.K.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 10-25-88

INV. NO. 22711

Signed Dale F. Balthazor
Dale F. Balthazor (TECHNICIAN)