

4-020068

11-23

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-167-21,492 -00-00
C E2 SE SW /4 SEC. 06 , 12 S, 14 W
660 feet from S section line
2970 feet from E section line

Operator license# 100

Lease: Stielow - Weiler<sup>ANB
KCC</sup> Well # 2

Operator: Kansas Corporation Commission
State of Kansas Fee Fund
Address: 2301 E. 13th Street
Hays, Kansas 67601
Control #990014-003

County: Russell
Well total depth 3328 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 199 feet

Aband. oil well Gas well Input well SWD D & A

Plugging contractor: Kansas Corporation Commission License# 100

Address: 2301 E. 13th Street - Hays, Kansas 67601

Company to plug at: Hour: 12:00 P.M. Day: 23 Month: November Year: 1998

Plugging proposal received from: Kansas Corporation Commission Dist #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Production perfs at 3032' - 3034' (Lansing).
WLFL at 2000' and WLTD 2970'.
Perforated well at the base of Dakota at 460'. Anhydrite at 885'.
Base of salt at 1475'.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All , Part , None

Completed: Hour: 1:30 P.M. , Day: 23, Month: November , Year: 1998

Actual plugging report: 8 5/8" set at 199'. 4 1/2" set at 3319'.
Tied onto 4 1/2" and pumped 225 sxs of 60/40 pozmix - 10% gel with 800# hulls.
Max. P.S.I. 200#. S.I.P. 100#.
Tied onto annulus and pumped 25 sxs cement with 50# hulls.
Max. P.S.I. 200#. S.I.P. 200#.

RECEIVED
KANSAS CORP COM
NOV 25 1998

11-25-98

Remarks:
Condition of casing(in hole): GOOD BAD
Bottom plug(in place): YES , CALC , NO
Plugged through TUBING , CASING
Anhy.plug: YES NO
Dakota plug: YES , NO
Elevation: 1758 GL

I did / did not observe the plugging.

[Signature]
(agent)

D.