

15-167-00364-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

NORTH



Locate well correctly on above  
Section Plat

Russell County. Sec. 29 Twp. 12 Rge. 14 (X) (W)  
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SE SE NE  
Lease Owner Crown Oil Company, Inc.  
Lease Name Foster Well No. 1  
Office Address Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed September 23, 19 49  
Application for plugging filed 9-26-50 19  
Application for plugging approved 9-26-50 19  
Plugging commenced 9-26-50 19  
Plugging completed 9-30-50 19  
Reason for abandonment of well or producing formation Production dropped to a point  
that it was unprofitable  
If a producing well is abandoned, date of last production September 19 50  
Was permission obtained from the Conservation Division or its agents, before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Kansas City Lime Depth to top 280 ft Bottom Total Depth of Well 2853 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|----|------|--------|------------|
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

14 sacks of cement on top of chat  
Hole was filled with chat to 2830' Then hole was filled with heavy rotary mud to 250' Put in rock bridge and run 15 sacks of cement then filled hole to 40' with mud then hole filled to surface with cement.

RECEIVED  
STATE CORPORATION  
FEB 21 1951  
02-21-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to  
Address

STATE OF Kansas, COUNTY OF Barton, ss.  
Dan H. Cook


(employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
described well as filed and that the same are true and correct. So help me God. Crown Oil Company, Inc.

(Signature) Dan H. Cook Secretary

(Address)

SUBSCRIBED AND SWORN to before me this 11th day of October 19 50

My commission expires 6-13-50  
Henry Peacock Notary Public.



WELL LOG

Crown Oil Co., Inc. et al  
FOSTER #1

Section 29-12-147  
SE 1/4 NE  
Russell County, Kansas

Total Depth 2853'  
Comm: 9/15/49; Comp. 9/23/49  
Contractor: Harms & Knight Drilling Co.  
Issued: 10/12/49 Rotary 0-2953

Elevations:  
Production:

Casing Record: 8 5/8" bot O 693, cemented with 500 sacks, circulated.  
5 1/2" bot O 2041, cemented with 75 sacks.

Figures indicate bottom of formation:

|                         |      |
|-------------------------|------|
| Collar                  | 6    |
| Shale                   | 50   |
| Sand                    | 135  |
| Shale and redbed        | 250  |
| Shale and shells        | 390  |
| Sand                    | 478  |
| Sand and redbed         | 600  |
| Red bed                 | 691  |
| Anhydrite               | 693  |
| Anhydrite and lime      | 728  |
| Redbed and shale        | 1105 |
| Shale, salt, and shells | 1400 |
| Red bed and shale       | 1400 |
| Shale and shells        | 1540 |
| Lime                    | 1690 |
| Shale and lime          | 1810 |
| Lime and shale          | 2425 |
| Shale                   | 2455 |
| Shale and shells        | 2555 |
| Lime and shale          | 2845 |
| Lime                    | 2853 |
| Total Depth             | 2853 |

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 27 1954  
CONSERVATION DIVISION  
Kansas  
Jefferson

We hereby certify this to be a correct and accurate log of the described well as shown on the daily drilling reports.

HARMS & KNIGHT DRILLING CO.

By: W. Harms

Subscribed and sworn to before me this 12th day of October, 1949.

Merle W. Sandberg  
Notary Public



PLUGGING  
FILE SEC 29-12-147  
BOOK PAGE 32 LINE 3