

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-167-22,978-00-00

LEASE NAME Paradise South

WELL NUMBER B #1

3630' Ft. from S Section Line

990' Ft. from E Section Line

SEC. 32 TWP. 12 RGE. 14 (E) or (W)

COUNTY Russell

Date Well Completed 6-18-91

Plugging Commenced 6-18-91

Plugging Completed 6-18-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR E.S.P. Development, Inc.

ADDRESS R.R. #1 Box 18, Paradise, Kansas 67658

PHONE#(913) 998-4413 OPERATORS LICENSE NO. 6194

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 13, 1991 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

Formation	Content	From	To	Size	Put In	Pulled out
	Surface Pipe	0	213'	8 5/8	7 jts.	0

STATE CORPORATION COMMISSION

07-02-91
JUL 02 1991

CONS. DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Plugs: 3187' 25sks, 775' 25sks, 450' 80sks, 40' 10sks, rat hole 15sks, Total 155sks,
60/40 poz, 6%gel, 1/4lb. flow seal per sks, Plug down @ 3:00 A.M. 6-18-91.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Western Kansas Drilling, Inc. License No. 4083

Address 117 E. 13th, P.O. Box 126, Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: E.S.P. Development, Inc.


STATE OF Kansas COUNTY OF Russell, ss.

Lewis Eulert (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Lewis Eulert

(Address) RR1, Box 18 Paradise KS 67658

SUBSCRIBED AND SWORN TO before me this 13th day of July, 19 91



Donna Super
Notary Public

My Commission Expires: 2-9-93

Operator: E.S.P. Development, Inc.

Contractor: Western Kansas Drilling, Inc.

Well & Well Description: Paradise South B #1
NW-SE-NE 32-12-14 Russell County, Kansas

Commenced: 6-11-91

Completed: 6-18-91

Character of Well: D & A

Elevation: 1705' GL 1710' KB

Casing: Ran 7 jts. of 8 5/8's set @ 213'

Figures Indicate Bottom of Formations

0' - 754'	Sand & Shale	3117' - 3210'	Lime & Shale
754' - 792'	Anhy.		
792' - 1406'	Shale		
1406' - 1880'	Sand & Shale		
1880' - 2278'	Shale		
2278' - 2915'	Lime & Shale		
2915' - 2949'	Lime		
2949' - 3040'	Lime & Shale		
3040' - 3117'	Lime		

State of Kansas)
County of Ellis) ss:

I Stanley Younger, President of Western Kansas Drilling, Inc. upon oath state that the above and foregoing is a true and correct copy of the log of the Paradise South B #1

RECEIVED
STATE CONSERVATION COMMISSION

Stanley Younger
Stanley Younger, President

JUL 02 1991

CONSERVATION DIVISION
Wichita, Kansas