

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Oil Producers of Kansas, Inc.
Address: 1710 Waterfront Parkway, Wichita, KS 67201
Phone: (316) 215-1357 Operator License #: 8061
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Steve Durant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Conglomerate Depth to Top: 4096' Bottom: 4130' T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-NW 145-20523-0000
Lease Name: Schartz A
Well Number: 1 AWSWSEAR
Spot Location (QQQQ): G - S1/2 - S1/2 - NE/4
2970 Feet from North / South Section Line 1326 Feet from East / West Section Line 3010
Sec. 7 Twp. 23 S. R. 16 East West
County: Pawnee
Date Well Completed: 7/11/78
Plugging Commenced: 04/30/09
Plugging Completed: 05/05/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	329'	
				4 1/2" 10.5#	4192'	2130'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 200# hulls, 30 sacks cement, displaced with 60 bbls. water, max pressure 1500', shot in 1000 psi, dug cellar, cement was at 3600', ripped 2510', ripped casing at 2250', ripped casing at 2130', pipe came free, pulled casing up to 1070', swedge in, had to pull trucks in, pumped 15 gel, 50 sacks cement, 100# hulls, pulled to 40', pumped 20 sacks to surface.


RECEIVED

MAY 28 2009

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
Address: 190 US Highway 56, Ellinwood, KS 67526

KCC WICHITA

Name of Party Responsible for Plugging Fees: Oil Producers of Kansas, Inc.
State of Kansas County, Sedgwick, ss.
Oil Producers Inc of Kansas (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]
(Address) 1710 Waterfront Parkway, Wichita, KS 67206

SUBSCRIBED and SWORN TO before me this 26 day of May, 2009
Lori A. Zehr My Commission Expires: May 5, 2010
Notary Public