

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

145-20538-00-00

Lease Operator: Oil Producers of Kansas, Inc.

Address: 1710 Waterfront Parkway, Wichita, KS 67201

Phone: (316) 215-1357 Operator License #: 8061

Type of Well: Gas Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: \_\_\_\_\_ (Date)

by: Steve Durant (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

Conglomerate Depth to Top: 4102' Bottom: 4134' T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-N/A

Lease Name: Schartz C

Well Number: 1

Spot Location (QQQQ): C - S/2 - N/2 - SE/4

1650 Feet from  North /  South Section Line

1320 Feet from  East /  West Section Line

Sec. 7 Twp. 23 S. R. 16  East  West

County: Pawnee

Date Well Completed: 1/19/1979

Plugging Commenced: 05/06/09

Plugging Completed: 05/07/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	351'	
				4 1/2" 10.5#	4198'	2030'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sanded off bottom, loaded hole with water, dug cellar, sand was at 4040', bailed 4 sacks cement with bailer, had 19' stretch, ripped casing at 2140', ripped casing at 2030', pulled casing up to 1070', pumped 15 gel, 50 sacks, 100# hulls, pulled up to 330', pumped 50 sacks, 100# hulls, pulled to 40', pumped 20 sacks to surface.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 190 US Highway 56, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: Oil Producers of Kansas, Inc.

State of Kansas County, Sedgwick, ss.

Oil Producers Inc. of Kansas (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct; so help me God.



(Signature) [Handwritten Signature]

(Address) 1710 Waterfront Parkway, Wichita, KS 67206

SUBSCRIBED and SWORN TO before me this 26th day of May, 2009

Lori A. Zehr My Commission Expires: May 5, 2010  
Notary Public

RECEIVED

MAY 28 2009

KCC WICHITA

[Handwritten initials]