

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

MAY 27 2009

Form CP-4

December 2003

Type or Print on this Form

Form must be Signed

All blanks must be Filled

Lease Operator: PETROLEUM PROPERTY SERVICES INC.

Address: 125 N. MARKET, SUITE 1251, WICHITA KS 67202

Phone: (316) 265-3351 Operator License #: 31142

Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 4/6/09 (Date)

by: STEVE PFEIFER (KCC District Agent's Name)

Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

MISS Depth to Top: 4867 Bottom: 4882 T.D. 4882

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-007-01198-0000

Lease Name: SKINNER D

Well Number: 7

Spot Location (QQQQ): NW - SW - SE - SW

351 Feet from ☐ North / ☒ South Section Line

3661 Feet from ☒ East / ☐ West Section Line

Sec. 3 Twp. 32 S. R. 15 ☐ East ☒ West

County: BARBER

Date Well Completed: 2/59

Plugging Commenced: 4/6/09

Plugging Completed: 4/08/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
MISS	OIL/WATER	4867	4882	8-5/8"	306	0
				5-1/2	4867	1980

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1ST PLUG @1200'. LOAD HOLE W/20 SX GEL, PUMP 50 SX 60/40,4%. 2ND PLUG AT 600' W/ 50 SX 60/40,4%

SET 3RD PLUG AT 330', W/20 SX 60/40, 4%. 4TH PLUG AT 40' W/35 SX 60/40,4%. CIRCULATED CEMENT TO SURFACE

Name of Plugging Contractor: H-D OILFIELD SERVICE License #: 32970

Address: P O BOX 87, BAZINE KS

Name of Party Responsible for Plugging Fees: PETROLEUM PROPERTY SERVICES INC.


State of KANSAS County, SEDGWICK, ss.

MICHEAL S MITCHELL

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____

(Address) 125 N. MARKET, SUITE 1251, WICHITA KS 67202



SUBSCRIBED and SWORN TO before me this 20TH day of MAY, 20 09
Rosann M. Schippers My Commission Expires: 9/28/11
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202