

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED MAY 27 2009 KCC WICHITA Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: FALCON EXPLORATION INC. Address: 125 N. MARKET, SUITE 1252, WICHITA KS 67202 Phone: (316) 262-1378 Operator License #: 5316 Type of Well: GAS Docket #: The plugging proposal was approved on: 4/9/09 by: RICHARD LACEY Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) MISS Depth to Top: 4360 Bottom: 4375 T.D. 4450

API Number: 15-007-21275-0000 Lease Name: HOAGLAND Well Number: 1 Spot Location (QQQQ): NW - NE - NW - NE 4964 Feet from North / South Section Line 1674 Feet from East / West Section Line Sec. 36 Twp. 31 S. R. 12 East West County: BARBER Date Well Completed: 10/81 Plugging Commenced: 4/13/09 Plugging Completed: 4/13/09

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: MISS, GAS, 4360, 4375, 8-5/8", 204, 0. Row 2: 4-1/2, 4448, 720'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

SET CIBP AT 4300'. DUMPED 2 SX CEMENT ON TOP AND PULLED 60,000 ON CASING AND IT PARTED. PULLED OUT 720' CASING. RAN TUBING TO 690' AND PUMPED 20 SX GEL AND 50 SX 60/40, 4% GEL, SET 2ND PLUG AT 240' AND PUMPED 50 SX 60/40, 4% GEL, SET 3RD PLUG AT 30' AND PUMPED 20 SX 60/40, 4% GEL, CIRCULATED CEMENT TO SURFACE.


Name of Plugging Contractor: H-D OILFIELD SERVICE License #: 32970 Address: P O BOX 87, BAZINE KS 6751

Name of Party Responsible for Plugging Fees: FALCON EXPLORATION INC. State of KANSAS County, SEDGWICK, ss.

MICHEAL S. MITCHEL (Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) 125 N. MARKET, SUITE 1252, WICHITA KS 67202



SUBSCRIBED and SWORN TO before me this 20TH day of MAY, 20 09

Rosann M. Schippers Notary Public My Commission Expires: 9/28/11

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]