

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 9067
Name: DaMar Resources, Inc.
Address 1: 234 W. 11th St.
Address 2: P. O. Box 70
City: Hays State: KS Zip: 67601 +
Contact Person: Curtis R. Longpine
Phone: (785) 625-0020
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Lans-KC Depth to Top: 2980 Bottom: 3250 T.D. 3400
Simpson Depth to Top: 3267 Bottom: 71 T.D. 3400
Arbuckle Depth to Top: 3278 Bottom: 3400+ T.D. 3400

API No. 15 - 053-20972 -0000
Spot Description: _____
SE SE NW NE Sec. 33 Twp. 16 S. R. 10 East West
4,230 Feet from North / South Line of Section
1,406 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellsworth
Lease Name: Schroeder Well #: 6
Date Well Completed: 12/85
The plugging proposal was approved on: 4/23/09 (Date)
by: Jeff Klock (KCC District Agent's Name)
Plugging Commenced: 4/23/09
Plugging Completed: 4/23/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		surface	8 5/8"	411	none
		productin	5 1/2"	3400	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIPB @ 2940, spot 4 sk cement on top of plug. Perforate 2 shots @ 1350'; 1000' and 460'. Plug with 60/40 poz w/4% gel as follows: 35 sx w/100# hulls @ 992, 45 sx from 465' to surface, no entry down annulus, pump 5 sx down 5 1/2 @ 500#. Shut in @ 300#.

RECEIVED

MAY 27 2009

Plugging Contractor License #: 32128 Name: Western Well Service
Address 1: 1023 Reservation Rd. Address 2: _____
City: Hays State: KS Zip: 67601 +
Phone: (785) 625-1118

Rome CORP DBA

KCC PKT

KCC WICHITA

Name of Party Responsible for Plugging Fees: DaMar Resources, Inc.
State of Kansas County, Ellis, ss.
Curtis R. Longpine Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Signature]

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT