

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5010
Name: Knighton Oil Company, Inc.
Address 1: 1700 N. waterfront Parkway, Bldg. 100-A
Address 2: _____
City: Wichita State: KS Zip: 67206 + _____
Contact Person: Earl M. Knighton, Jr
Phone: (316) 630-9905
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing Depth to Top: 1414 Bottom: 1420 T.D. 1653
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 127-205540000
Spot Description: _____
S NW NW SW Sec. 11 Twp. 16 S. R. 7 East West
2,310 Feet from North / South Line of Section
330 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Morris
Lease Name: Leeds Well #: 1
Date Well Completed: 6/14/1995
The plugging proposal was approved on: 5/20/09 (Date)
by: Greg Eves (KCC District Agent's Name)
Plugging Commenced: 5/20/09
Plugging Completed: 5/21/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	184'	None
		Production	4 1/2"	1653	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf-Tech: Set 4 1/2" Alpha M-2 CIBP at 1370'. Glass bottom dump bailer run, 2 sacks cement on plug at 1370'. Perforated to plug well, 2 holes at 250'.

Consolidated: Safety meeting, rig up to 4 1/2" casing, break circulation, pumped 100 sacks 60/40 poz, 4% gel. Circulated from 250' perfs around backside in the cellar.

Wash up and rig down.

RECEIVED

MAY 29 2009

KCC WICHITA

Plugging Contractor License #: 34016 5010 Name: Ruf Nek Well Service & Supply
Address 1: P.O. Box 1580 Address 2: _____
City: Lincolnville State: KS Zip: 66858 + 0159
Phone: (620) 942-5717
Name of Party Responsible for Plugging Fees: Knighton Oil Company, Inc.
State of Kansas County, Sedgwick, ss.
David D. Montague Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

pen

Perf-Tech

Wireline Services, Inc.

P.O. Box 87
 HAYS, KS 67601-0087
 (785) 623-3969

Invoice

DATE	INVOICE #
5/21/2009	6544

BILL TO
Knighton Oil Co. P.O. Box 1580 Hays Kansas 67601

RECEIVED
 MAY 29 2009
 KCC WICHITA

SERVICE DATE	DESCRIPTION	ITEM	AMOUNT
5/20/2009	Leeds #1 Morris County Kansas Set 4 1/2" Alpha M-2 CIBP at 1370' Glass bottom dump bailer run, 2 sx cement on plug at 1370' Perforated to plug well. 2 holes at 250'	PERF	1,350.00T
	Truck Rental	Truck set up	400.00T
	Sales Tax		92.75

*LEEDS #1
 SET PLUG &
 PERFORATE
 FOR PLUGGING*

Price reflects discount Thank You for your business!!	Total	\$1,842.75
--	--------------	------------

WELL FILE

Perf-Tech

Wireline Services, Inc.

6544

P.O. Box 87
Hays, KS 67601-0087

Job Ticket

DATE 5-20-09

CHARGE TO Knighton 011

ADDRESS _____

LEASE AND WELL NO. LEEDS #1 FIELD _____

NEAREST TOWN _____ COUNTY MORRIS STATE KS

CUSTOMER'S ORDER NO. _____ SEC. _____ TWP. _____ RANGE _____

ZERO _____ CASING SIZE 4 1/2 WEIGHT _____

CUSTOMER'S T.D. _____ PERF TECH T.D. _____ FLUID LEVEL 500

ENGINEER DEAN OPERATOR JESSIE J. J.

PERFORATING					
CODE REFERENCE	DESCRIPTION	NO HOLES	DEPTH FROM TO		AMOUNT
	<u>11 gm 2 Per</u>				
		<u>2</u>	<u>1370</u>		

PLUGS, PACKERS AND OTHER					
CODE REFERENCE	MFG. TYPE	CASING SIZE WEIGHT		DEPTH	AMOUNT
	<u>4 1/2 CIPD</u>			<u>1370</u>	
	<u>2 SX cement</u>				

TRUCK RENTAL			
CODE REFERENCE	RUN NO.	PREVIOUS INVOICE NO.	AMOUNT

DEPTH OF OPERATIONS CHARGES					
CODE REFERENCE	FROM	TO	NO. FEET	PRICE PER FT.	AMOUNT

RECEIVED MAY 29 2009 KCC WICHITA PLEASE PAY FROM THIS INVOICE TOTAL	SUB TOTAL TAX	
---	--------------------------------	--

RECEIVED THE ABOVE SERVICE ACCORDING TO THE TERMS AND CONDITIONS SPECIFIED BELOW WHICH WE HAVE READ AND TO WHICH WE HEREBY AGREE

Customer [Signature]

General Terms and Conditions

- (1) All accounts are to be paid within the terms fixed by Perf-Tech invoices; and should these terms not be observed, interest at the rate of 1.5% per month will be charged from the date of such invoice.
- (2) Because of the uncertain conditions existing in a well which are beyond the control of Perf-Tech, it is understood by the customer that Perf-Tech, cannot guarantee the results of their services and will not be held responsible for personal or property damage in the performance of their services.
- (3) Should any of Perf-Tech, instruments be lost or damaged in the performance of the operations requested, the customer agrees to make every reasonable effort to recover same, and to reimburse Perf-Tech, for the value of the items which cannot be recovered, or the cost of repairing damage to items recovered.
- (4) It is further understood and agreed that all depth measurements shall be supervised by the customer or its employees and customer hereby certifies that the zones, as shot were approved.
- (5) The customer certifies that it has the full right and authority to order such work on such well and that the well in which the work is to be done by Perf-Tech is in proper and suitable conditions for the performance of said work.
- (6) No employee is authorized to alter the terms or conditions of this agreement.

WELL FILE



CONSOLIDATED
Oil Well Services, LLC

ENTERED

TICKET NUMBER 20927
LOCATION El Dorado #80
FOREMAN Jim Thomas

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
5-21-09	4495	Leeds #1, Trowbridge #1				Monro
CUSTOMER Knighton Oil Co			TRUCK # DRIVER TRUCK # DRIVER			
MAILING ADDRESS 221 S. Broadway Suite 710						
CITY Wichita		STATE KS	ZIP CODE 67202			

JOB TYPE Plug HOLE SIZE _____ HOLE DEPTH _____ CASING SIZE & WEIGHT 4 1/2", 5 1/2"
CASING DEPTH _____ DRILL PIPE _____ TUBING _____ OTHER _____
SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety Meeting Rig up to 4 1/2" Brake circulation, Pump 100 sks 60/40 poz 4% gel, Circulated from 250 ft. "Perfs" around backside in the cellar. 2nd Well Pumped 94 sks 60/40 poz 4% gel down 5 1/2" casing cement circulated around backside from 250 ft. to surface. Cement circulated in the cellar. Wash up & Rig down.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405A	1	PUMP CHARGE	590.00	590.00
5406	55	MILEAGE	3.45	189.75
5405A	2nd	well charge	400.00	400.00
1131	1945 sks	60/40 poz	10.70	2075.80
1138A	300 lbs	gel	.16	138.00
5502C	8 hrs	80 BDh Vac Truck	94.00	752.00
5407A	10.0 Tons	55 miles Bulk Del.	1.16	658.00
		RECEIVED		
		MAY 29 2009		
		KCC WICHITA		
		<u>subtotal</u>		4773.55
			SALES TAX	138.84
			ESTIMATED TOTAL	4912.39


Rev'n 3737

AUTHORIZATION [Signature]

TITLE _____

DATE 5-21-09

029718



CONSOLIDATED
Oil Well Services, LLC

REMIT TO
Consolidated Oil Well Services, LLC
Dept. 970
P.O. Box 4346
Houston, TX 77210-4346

MAIN OFFICE
P.O. Box 884
Chanute, KS 66720
620/431-9210 • 1-800/467-8676
FAX 620/431-0012

INVOICE

Invoice # 229718

Invoice Date: 05/26/2009 Terms:

Page 1

KNIGHTON OIL CO
BUILDING 100 SUITE A
1700 N. WATERFRON PARKWAY
WICHITA KS 67206
(316)264-7918

LEEDS #1, TROWBRIDGE #1
20927
05-21-09

Part Number	Description	Qty	Unit Price	Total
1131	60/40 POZ MIX	194.00	10.7000	2075.80
1118A	S-5 GEL/ BENTONITE (50#)	800.00	.1600	128.00

Description	Hours	Unit Price	Total
290 P & A OLD WELL	1.00	590.00	590.00
290 EQUIPMENT MILEAGE (ONE WAY)	55.00	3.45	189.75
290 P & A OLD WELL	1.00	400.00	400.00
434 80 BBL VACUUM TRUCK (CEMENT)	8.00	94.00	752.00
439 TON MILEAGE DELIVERY	550.00	1.16	638.00

RECEIVED
MAY 29 2009
KCC WICHITA

Parts:	2203.80	Freight:	.00	Tax:	138.84	AR	4912.39
Labor:	.00	Misc:	.00	Total:	4912.39		
Sublt:	.00	Supplies:	.00	Change:	.00		

Signed _____ Date _____