

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5610
Name: Bruce Oil Company
Address 1: 1704 Limestone Road
Address 2: _____
City: McPherson State: KS Zip: 67460 + _____
Contact Person: Lonny Bruce
Phone: (620) 241-2938
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: D-5550
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
SWD Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 159-03657-00-00
6-22-56
Spot Description: _____
approx NE NE SE Sec. 32 Twp. 20 S. R. 7 East West
2,307 Feet from North / South Line of Section
423 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Rice
Lease Name: Barker Well #: 3
Date Well Completed: 6-22-56
The plugging proposal was approved on: 4-10-2009 (Date)
by: Virgil Clothier (KCC District Agent's Name)
Plugging Commenced: 4-10-2009
Plugging Completed: 4-21-2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Surface	soil, shale, sand		8 5/8	227	None
Arbuckle	dolomite, lime		5 1/2	3743	1430

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing to 3293 on 4-10-09, spotted 75 sax cement, found cement at 3176 on 4-13-09, pulled 46 joints of casing on 4-17-09, ran tubing to 1150 and spotted 35 sax cement on 4-20-09, found cement at 1120 after 1 hour, pulled tubing to 595 and spotted 35 sax cement, did not find cement after one hour, spotted another 35 sax cement at 595, found cement at 475 after two hours, pulled tubing to 279 and circulated cement to surface. Found cement at surface on 4-21-09. Plugging complete.

Plugging Contractor License #: 30280 Name: Sunflower Well Service Inc
Address 1: Box 341 Address 2: _____
City: Canton State: Kansas Zip: 67428 + 0321
Phone: (620) 628-4723
Name of Party Responsible for Plugging Fees: Bruce Oil Company, L.L.C.
State of Kansas County, McPherson, ss.
Lonny Bruce Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Lonny Bruce

RECEIVED

MAY 29 2009

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC WICHITA

BENNETT & GOULD

#3 BARKER

32-20-7W
NE NE SE

Contr. BENNETT & ROBERTS

RICE County


E 1624 RB Comm. Comp. 6-22-56 IP

D & A

Tops	Depth	Datum
HEEB	2691	-1067
TOR	2708	-1084
DOUG	2713	-1089
BR LM	2851	-1227
LANS	2876	-1252
B/KC	3215	-1591
SH CONG	3308	-1684
CH CONG	3325	-1701
TD	3339	-1715

Casing
8" 227

WHERRY POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

RECEIVED
MAY 29 2009
KCC WICHITA