

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R. -82-3-117

15-109-20669-00-00

API NUMBER 15-109-20669

LEASE NAME BERTRAND "B"

WELL NUMBER 1-11

TYPE OR PRINT
NOTICE- Fill out completely
and return to Cons. Div.
office within 30 days.

1650 Ft. from S Section Line

2270 Ft. from E Section Line

SEC. 11 TWP. 11s RGE. 34w E W

COUNTY Logan

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 3017 N. Cypress Street, Wichita, KS 67226-4003

PHONE # (316) 636-2737 OPERATORS LICENSE NO. 5003

Date Well Completed 6/18/98

Character of Well D&A

RECEIVED
STATE CORPORATION COMMISSION

Plugging Commenced 6/18/98

(Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging Completed 6/18/98

The plugging proposal was approved on 7-10-1998 6/18/98 (date)

by Herb Deines (KCC District Agent's Name),

Is ACO-I filed? Yes If not, Is well log attached? No

Producing Formation None Depth to Top NA Bottom NA T.D. 4765'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface		0	252'	8 5/8"	252'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

P&A using 200 sk 60/40 poz, 6% gel. 1/4# floseal p/sk, 1st plug @ 2670' w/25sx, 2nd plug @ 1575' w/100sx, 3rd plug @ 305' w/40sx, 4th plug @ 40' w/10sx, 15sx in rathole & 10sx in mousehole. P.D. @ 10:30 p.m. by Halliburton.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard JV, Inc. License No. 4958

Address P.O. Box 1009, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES McCoy Petroleum Corporation


STATE OF Kansas COUNTY OF Sedgwick ss.

Corey N. Baker, Regulatory Geologist, (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Corey N. Baker

(Address) 3017 N. Cypress Street, Wichita, KS 67226-4003

SUBSCRIBED AND SWORN TO before me this 9th day of July, 19 98



Deborah Ann Paulus
Notary Public

January 8, 2000