

STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

K.A.R.-82-3-117

API NUMBER 109-20633 0000

LEASE NAME Hubert "E"

15-109-20633-00-00
TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 25 TWP. 11S RGE. 34 X (W)

COUNTY Logan

Date Well Completed 10/27/96

Plugging Commenced 12:15AM 10/27/96

Plugging Completed 3:30AM 10/27/96

LEASE OPERATOR AFG Energy, Inc.

ADDRESS P.O. Box 458 Hays, Kansas 67601

PHONE (913) 625-6374 OPERATORS LICENSE NO. 3456

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/25/96 (date)

by Ken Kuhn (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? Yes

Producing Formation None Depth to Top Bottom T.D. 4805

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|-----|-------|--------|------------|
| | | 0 | 296 | 8 5/8 | 296.17 | None |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section.

1st Plug @ 2650'w/25sk 10sk In Mouse Hole Circulated 1st Plug 15 Minutes with 51 V/S Mud
 2nd Plug @ 1560'w/100sk 15sk In Rat Hole Plugs displaced with mud
 3rd Plug @ 350'w/40sk Total 200sk 60/40 Poz 6%Gelw/1#FS/sk By Allied Cementing
 4th Plug @ 40'w/10sk Job Completed @ 3:30AM 10/27/96

Name of Plugging Contractor Discovery Drilling, Inc. License No. 31548

Address P.O. Box 763 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AFG Energy, Inc.

STATE OF KANSAS COUNTY OF ELLIS, ss.

EDGAR L. GLASSMAN

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar L. Glassman

(Address) P.O. Box 458; Hays, KS 67601



AND SWORN TO before me this 1st day of Nov, 19 96

Linda K. Pfannenstiel
Notary Public

My Commission Expires: 2/5/2000

USE ONLY ONE SIDE OF EACH FORM