

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER No Api#-drilling completion date 1-17-52 6/86  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Kaiser-Francis Oil Company OPERATORS LICENSE NO. 6568

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468 PHONE # (918) 494-0000

LEASE (FARM) RIDLER C WELL NO. 1 WELL LOCATION SW SE NW COUNTY Rooks

SEC. 31 TWP. 10S RGE. 17 (W) TOTAL DEPTH 3657 PLUG BACK TD 3494

Check One:

OIL WELL  GAS WELL \_\_\_\_\_ D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8-5/8 SET AT 1381 CEMENTED WITH 700 SACKS

CASING SIZE 4-1/2 SET AT 3656 CEMENTED WITH 200 SACKS

PERFORATED AT 3295-2477 O.A.

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Set CIBP @ 3250'. Dump 20' cement on CIBP. Locate Free Pt. Shoot off casing. Spot 50 SX cement at casing stub.

Pull casing. Spot cement plug 100' in & out of surface pipe. Cement 40' to Surf.  
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? on old form  
(If not, explain) (Form was not in file)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:  
Glenn Jackson - Superintendent PHONE # (316) 564-3214

ADDRESS P. O. Box 666, Ellinwood, KS 67526

PLUGGING CONTRACTOR Kelso Casing Pullers LICENSE NO. 6050

ADDRESS P. O. Box 176, Chase, KS 67524 PHONE # (316) 938-2457

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]  
(Operator or Agent)

6

STATE CORPORATION COMMISSION

APR - 4 1985

4-4-86  
CONSERVATION DIVISION

DATE: 4/1/86



JOHN CARLIN  
MICHAEL LENNEN  
ARGALEE WRIGHT  
EITH R. HENLEY  
JUDITH A. McCONNELL  
ARIAN J. MOLINE

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary  
General Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
200 Colorado Derby Building  
202 West 1st Street  
WICHITA, KANSAS 67202-1286

THIS NOTICE

JUL 4 1986

April 4, 1986

EXPIRES

WELL PLUGGING NOTICE

Ridler C #1  
SW SE NW  
Sec. 31-10S-17W  
Rooks County

Kaiser-Francis Oil Company  
P. O. Box 21468  
Tulsa, OK 74121-1468

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson, Director

Please contact the district office to review your suggested method of plugging

DIST. #6 1014 Cody Hays, KS 67601 913-628-1200

five days prior to plugging the well (KAR-82-3-113).