

15-109-20447-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev.03/92

RECEIVED

AUG 16 2002
8-16-2002
KCC WICHITA

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-109-20447 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Novy Oil & Gas, Inc. KCC LICENSE # 31714
(owner/company name) (operator's)

ADDRESS 125 N. Market, Suite 1230 CITY Wichita

STATE KS ZIP CODE 67202 CONTACT PHONE # (316) 265-4651

LEASE Bertrand "Z" WELL# 1 SEC. 35 T. 11S R. 33 (East/West)

- NW - NW - NW SPOT LOCATION/QQQQ COUNTY Logan

4840' FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

4840' FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 223' CEMENTED WITH 200 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4674' CEMENTED WITH 200 SACKS

DV tool @ 2538' w/550 sx circ. to surface
LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: perfs 4422-28, 4266-85, 4192-98, 4122-24
CIBP @ 4215'

ELEVATION 3095 GL T.D. 4675' PBSD 4654' ANHYDRITE DEPTH 2590'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Pump 15 sx. cmt. down backside - tie into 4 1/2" casing &
pump 50 sx. cmt. w/400# hulls, 20 sx. gel & 150 sx. 60/40 poz, 10% gel

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Michael E. Novy PHONE# (316) 265-4651

ADDRESS 125 N. Market, Suite 1230 City/State Wichita, KS 67202

PLUGGING CONTRACTOR Mike's Testing & Salvage KCC LICENSE # 31529
(company name) (contractor's)

ADDRESS P.O. Box 467, Chase, KS 67524 PHONE # (620) 938-2943

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8/10/02 AUTHORIZED OPERATOR/AGENT: Michael E. Novy
(signature)



15-109-20447-00-00

Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Novy Oil & Gas, Inc.
125 N. Market Ste. 1230
Wichita, KS 67202-1712

August 19, 2002

Re: BERTRAND Z #1
API 15-109-20447-00-00
SENWNWNW 35-11S-33W, 4840 FSL 4840 FEL
LOGAN COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550

Sincerely

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

Well

PLAN-O-GRAM

API-15-109-20,447

Company Novy Oil & Gas, Inc.

Well No. 1 Lease BERTRAND 'Z'

NW-NW-NW Sec 35-11S-33W Logan Co., KS.
4,840' FSL & 4,840' FEL
Elev- 3095 Gr. = 3102 KB

•			

RECEIVED
8-16-2002
AUG 16 2002
KCC WICHITA

8 5/8" @ 223' W/200 SX

167-3/4" Rods Pump- 2" x 1 1/2" x 12" BHD.

129 JTS-2 3/8" @ 4209
EIDER Tbg. Anchor- 2nd Jt. OFF Btm. APPROX @ 4145 W/22" ST
40,000# Shear PINS

DV tool @ 2538 W/550 SX. Cir. Cmt. to Surface

TOP CMT @ 3588 - BOND LOG

Perf-4112-16-'E'zn-500G. Acid-Test 6 BFPH-93% oil

Perf 4122-24 'F'zn-Test 2.5 BFPH-84% oil-1000G. Acid-Communicate TO'E

Perf 4192-98 'H'zn. 1500G. Acid-Test 0.5 BFPH 79% Wtr

CIBP @ 4215

Perf-4266-85-'K'zn. Acid-1000G.-Test 3 BFPH 98% Wtr.

Perf 4422-28 - Tight. No Acid Can be Pumped, ALTAMONT Zone

PBTD @ 4654

4 1/2" @ 4674 W/200 SX

Phase 1 - IP-50 BOPD-5BW- E-H-I Zone
11-1-1987

Phase 2 w/o - No IP- E-F-H ZONES
12-19-1992

Cementing

Special Tools

Acidizing

Chemical Services

Formation Testing

Fracturing

Dump Bailer

Casing Equipment

