

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20606-00-00
Spot: NWNENW Sec/Twnshp/Rge: 29-3S-36W
4950 feet from S Section Line, 3630 feet from E Section Line
Lease Name: CELIA SOUTH WF UNIT Well #: B-2
County: RAWLINS Total Vertical Depth: 4740 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	379	0	275 SX
PROD	5.5	4739	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/29/2009 1:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 462-1031

Proposed Plugging Method: Ordered 575 sxs 60/40 pozmix - 4% gel - 700# hulls.
Plug through tubing.

154.05

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/29/2009 4:45 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 379' w/275 sxs cement.
5 1/2" production casing set at 4739' w/200 sxs cement.
PBTD 4725'. TOC at 3950'.
Casing holes squeezed at 2468' - 2494' w/150 sxs; 2521' - 2820' w/200 sxs.
Ran tubing to 2600' - pumped 250 sxs cement with 700# hulls.
Cement to surface. Pulled tubing to surface.
Connected to 5 1/2" production casing - pumped 65 sxs cement.
Max. P.S.I. 600#. S.I.P. 400#.
Connected to 8 5/8" surface casing - pumped 80 sxs cement.
Max. P.S.I. 150#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
4656	4663		CHEROKEE W/ 4SP

INVOICED
DATE 6-8-09
INV. NO. 2009061572

KANSAS CORPORATION COMMISSION

MAY 07 2009
RECEIVED

Remarks: LEASE ORIGINALLY KNOWN AS HUBBARD #D-1. SWIFT SERVICES, INC.-TICKET #15,934.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

Form CP-2/3

APR 30 2009

JPT

CITIES SERVICE OIL &
GAS CORPORATION

209 E. WILLIAM, #700

WICHITA, KS. 67202

#1 'D' HUBBARD

29-3-36W

NW NE NW

CONTR MURFIN DRILLING

CTY RAWLINS

GEOL JIM BRUGGEMAN

FIELD CELIA EXT (1/8 W)


ELV 3296 KB SPD 5/9/85
3291 GL

CARD
ISSUED

8/22/85

IP P 34 BO & 3 BLWPD

CHER 4656-4663



LOG	Tops	Depth/Datum
HEEB	4129- 833
LANS	4184- 888
BKC	4467-1171
MARM	4479-1183
PAW	4537-1241
FT SC	4580-1284
CHER	4627-1331
LTD	4739-1443
RTD	4740-1444

API 15-153-20,606

8 5/8 " 379 / 275SX, 5 1/2 " 4739 / 200SX

DST (1) 4622-75 (CHER) / 30-60-45-60, REC 20' OCM, 1' OIL,
SIP 867-651#, FP 43-43 / 43-43#

MICT - CO, PF (CHER) 4656-63, AC 1000G (15%), SWB DWN,
SO, POP, P 1 BO & 3 BW / 24 HRS, OFF PMP, FRAC 400B GEL &
6500# 20/40 SD & 4000# 12/20 SD, 427 BTL, POP, P 35 BO & 4
BW / 24 HRS (8/5/85), 184 BL TO REC, P 34 BO & 3 BLW / 24
HRS (8/13/85), 168 BLW TO REC

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS