

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-023-20959-00-00  
Spot: SESESE Sec/Twnshp/Rge: 35-5S-42W  
435 feet from S Section Line, 575 feet from E Section Line  
Lease Name: SCHRITTER Well #: 44-35  
County: CHEYENNE Total Vertical Depth: 375 feet

Operator License No.: 33325  
Op Name: PETROLEUM DEVELOPMENT CORPOR  
Address: 1775 SHERMAN ST, STE 3000  
DENVER, CO 80203

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	375	0	W/100 SXS

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/27/2009 1:00 PM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: CHAD SAILORS Company: PETROLEUM DEVELOPMENT COR Phone: (970) 332-3520

Proposed Plug Method: Ordered 40 sxs 60/40 pozmix - 4% gel.  
Plug through coiled tubing.

35.00

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/27/2009 2:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

7" surface casing set at 375' w/100 sxs cement.  
Production string was not set.  
Ran coiled tubing to 290' - contacted cement - pumped 28 sxs cement.  
Cement to surface. Pulled coiled tubing to surface. Plug complete.  
Note: Cement yield 2.45 cubic ft/sx 12# ppg. Compressive strength 8/233, 48/900.

INVOICED  
DATE 6-8-09  
INV. NO. 2009061574

KANSAS CORPORATION COMMISSION

MAY 07 2009  
RECEIVED

Remarks: SANJEL SERVICE COMPANY-TICKET #9134794.

Plugged through: TBG

District: 04

Signed

*Darrel Dipman*

(TECHNICIAN)

CM

Form CP-2/3

*PT*

APR 28 2009

PETROLEUM DEVELOPMENT CORP  
DENVER CO 80203

**35-05S-42W**  
435'FSL & 575'FEL, SEC (IRREG)  
KANSAS

#44-35 SCHRITTER

City: CHEYENNE

Spot: NW SE SE SE API 15-023-20959

Site: 13-1/4 S & 9-1/2 W OF ST FRANCIS KS

Lat/Long: 39.56947 -101.99616

Field: CHERRY CREEK NIOBRARA GAS AREA EXT (2-3/4 S)

D&A


FR: 01/23/2008 Spd: 03/28/2008 Drtg Cp: 03/28/2008 Issued: 03/09/2009 Revised: 03/09/2009

Copyright 2009 Independent Oil & Gas Service, Inc. Wichita, KS

Side 1

**IP Status:**

**D&A, NIOB, 12/23/2008**

**Contr:** ADVANCED DRILLING TECHNOLOGIES #114

**Elev:** 3794 KB, 3782 GL, 3793 DF

**Formation Tops:** (L-Log, S-Sample, D-Driller)

NO TOPS RPTD

ERTD

1750 +2044

**Csg:** 7" 375 / 100 SX (ALT 1)

**Find:**

COMMENT: PROPOSED START 1/31/2008; SURF

CSG SET AHEAD 3/28/2008; DECISION MADE TO

ABD WELL PRIOR TO DRILLING PROD

WELLBORE

NO CORES OR DSTS

**Comp Info:** TRGT ZN: NIOB (GAS), PTD 1750

(NIOB), SI - EVAL, DECISION MADE TO P & A

(PLUG APPL FILED 12/23/2008) - TIGHT HOLE -

NO OTHER INFO AVAILABLE - TEMP COMP

3/9/2009